



KERALA CO-OPERATIVE MILK MARKETING FEDERATION LTD.
CENTRAL PRODUCTS DAIRY, PUNNAPRA P.O, ALAPPUZHA – 688 004.
Tel: 0477-2255900, 2255999,2255921, E-mail: cpd@milma.com
GST:32AAAK5375M4ZD

29.01.2025

CPD/Engg/524/2024-25

Sir,

Sub: Quotation notice for the Dismantling the tiles and installation of Stainless steel cladding in front of the milk silos at Central Products Dairy, Punnapra- reg.

Please furnish your sealed quotation for the Dismantling the tiles and installation of Stainless steel cladding in front of the milk silos at Central Products Dairy, Punnapra, as per the schedule of quantities and terms & conditions furnished below:

Scope of work

1. Dismantling and reinstallation of milk processing lines without affecting the daily activities and as per the instruction of engineer in charge.
2. Dismantle the existing tiles, chipping of existing concrete, installation of necessary reinforcement support, insertion of fasteners, installation stainless steel plate.
3. Provide suitable slope to avoid water clogging. Make the use of existing drains. Provide additional drainage with necessary fittings if necessary.
4. Stainless cladding sheet must overlap with the existing wall cladding and must be properly fixed and necessary concreting, plastering/grouting must required at the sides of the cladding sheet (8'x4").
5. Approx. area to be covered 15m x 3m and over lap of sheet must be 3" (three inch). The area specified may vary either side. However payment will be against the actual work done (up to max. of 45sq. m) and nothing will be paid extra.
6. Milma engineers are permitted to inspect all the materials at any point of time. After the entire work Work a site inspection will be conducted and immediate steps must be taken to clear the punch items must be cleared.
7. The entire work must be completed within 45 days from the receipt of work order

Terms and conditions.

1. The rate quoted should be inclusive of GST and nothing will be paid extra on this account.
2. All the works shall be carried out in your Engineering workshop as per the directions of our plant Engineer.
3. All materials (except stainless cladding sheet) and all the necessary tools & tackles for the work shall be arranged by you.
4. The entire works shall be completed as per our Plant Engineer instructions from time to time to complete the work within 45 days from the receipt of work order.

5. The CPD, Punnapra shall not be liable for any property damage or compensation in consequence to any accidents or mishap to any workman or other persons.
6. Work found inferior in quality/ workmanship on completion shall be redone at contractor's risk and cost.
7. All materials/debris/tools/equipments, etc, shall be completely removed from the site as per the instruction of our Maintenance Engineer.
8. Payment: 90% payment will be released after the successful completion of the works and the submission of original invoices and balance 10% will be release only after the guarantee period of six months.
9. Sealed quotations superscribed with "**Dismantling the tiles and installation of Stainless steel cladding at Central Products Dairy, Punnapra**" or shall reach our office on or before 2.00 P.M on 10.02.2025 and will be opened at 3:00 P.M on the same day.
10. Right to reject or cancel any or all quotations without assigning any reasons therefore is reserved with the undersigned. The acceptance of the quotations lies with the Manager, Central Products Dairy, Punnapra, Alappuzha.

Yours sincerely,


MANAGER