



KERALA CO-OPERATIVE MILK MARKETING FEDERATION LTD.
CATTLE FEED PLANT, PATTANAKKAD P.O, ALAPPUZHA – PIN 688 531
Tel: 0478-2831100, 2831122, 2831112-124, E-mail: cfp@milma.com
GST NO32AAAK5375M1ZG

No: CFPT/PE/555/2025-26

20.02.2025

Sub:-Enquiry for the Design, supply of materials, fabrication and erection of new MS galvanized walk way from existing walkway of old maize silo top to new walkway at bottom hopper silo top at our cattle Feed Plant, Pattanakad.

Sealed Quotations are invited from experienced contractors in structural fabrication and erection works for the above mentioned works, at our Cattle Feed Plant Pattanakad.

Scope of work

The scope of work involves supply and installation of new MS galvanized plat form from existing walkway of old maize silo top to new walkway at bottom hopper silo top with necessary supports and provision to lift a load of min. (1.5MT) from ground level at our Cattle feed Plant, Pattanakad.

Schedule of quantity.

MS galvanized walkway size approx. 12M length x 0.735 M width with necessary equally spaced bracing, handrail height of 1M necessary supports and grating.

PRICE

Prices and charges quoted shall be firm and fixed during the entire period of contract and shall not be subject to any variation or escalation whatsoever on any account.

General Conditions

1. An **EMD of Rs.5000/-** has to paid in advance through NEFT/RTGS/cash in favour of Manager, Cattle Feed Plant, Pattanakad.
2. The entire work shall be completed within 40 days from the date of receipt of the work order.
3. Work found inferior in quality/workmanship on completion shall be redone at contractor's risk and cost.
4. The contractor shall guarantee to rectify any defect on this work undertaken due to bad workmanship within six months from the date of completion of the work.
5. Each item of work shall be approved prior to commencement of the next work.
6. The contractor will be permitted to carry out the work only after the receipt of work permit issued by our Maintenance Engineer. The validity of the permit is one day only; if the work is not completed within a day a fresh permit shall be taken on next day.

8. Ensure all the welded portion must be painted.
7. The contractor shall arrange for all compliance to the ESI/PF rules in force. Cattle Feed Plant shall not be liable for any benefits/compensation to the workers engaged by the contractor, in the event of accidents/mishaps etc. during execution of work. The contractor shall provide suitable safety measures to Workers.
8. The contractor or his workmen shall not interfere in any activity of the Plant and/or cause any damages to buildings/property. The entry of all such laborers will be on the basis of gate pass, which will have to be arranged by the Contractor prior to starting the work. In the event of any damage to Cattle Feed Plant's property, the contractor alone shall be liable.
9. Interested contractors are invited to visit the plant on all working days from 10am to 4pm before participating in the tender.
10. Interested participants have to enclose the drawing for the entire plat form along with the quotation submitted.
11. Use only galvanized materials only confirms with STD ISO1461. Galvanizing thickness minimum 360g/m² to 500g/m² depending upon the thickness.
10. Applicable statutory deductions if any shall be effected while settling bills.

The sealed quotation super scribed with "Design, supply, fabrication and erection. of new MS galvanized platform" shall reach our office on or before 06.03.2026 3.00 pm on and will be opened at 3.30 pm on the same day.

Our bank details

**KCMMF LTD Cattle Feed Plant, Pattanakkad, Current Account No. 57042309686,
State Bank of India, Pattanakkad Branch,**

The Manager reserves the right to accept any or reject all the quotations without assigning any reasons.

Soumya R Nair
Digitally signed
by Soumya R Nair
Date: 2026.02.20
16:49:22 +05'30'

UNIT HEAD