



Kerala Co-operative Milk Marketing Federation Limited
Cattle Feed Plant, Malampuzha, Palakkad - 678651
Phone: 0491-2816301 Website: www.milma.com, E mail: cfm@milma.com
GST: AAAAK5375M6ZB (PAN: AAAAK5375M)

Enquiry No: CFP-M/PRODN/150/2024-25/20/540

06.05.2024

QUOTATION NOTICE

SUBJECT: SUPPLY CUM LAYING OF RS485 DATA CABLE ALONG WITH POWER CABLE AND FOR INSTALLING SILO RADAR LEVEL SENSOR – reg.

Sealed price quotations are invited from experienced electrical contractors for supply and laying of shielded cable and for mounting of Radar Level Sensor on the silo roof at Milma Cattle Feed Plant, Malampuzha.

SCOPE OF WORK

Supply and laying of shielded power cable along with RS485 data cable through 20mm PVC /25 mm GI conduit /building walls /building surfaces/cable trenches /cable trays etc. and Fixing Five beam 3D Radar Level Sensor on the silo roof.

The detailed description of work and the related materials required are as listed in ANNEXURE – 1 enclosed herewith.

GENERAL TERMS & CONDITIONS

1. Applicable statutory deductions like GST, income tax, sales tax, EPF/ESI, Work contract tax, etc. shall be effected while settling bills. The contractors must remit GST for the work and ESI/EPF for their employees. Also the contractor shall produce proof of remittance (Challan) along with bills to avoid the EPF/ESI cutting while submitting the bills and for considering release of payment. Bills without the ESI/EPF remittance proof will be settled only after cutting the statutory ESI/EPF from the bills.
2. All essential materials required for the work shall be brought to the site before commencing the work. The materials/tools & tackles brought inside our plant shall be properly listed and submitted to our Engineers for verification before in & out.

3. The supply order materials shall be inspected by our Engineers before acceptance for the said work. The materials shall be of our approved make as per the schedule of work order.
4. Each item of work as per work order shall be approved by our Engineers prior to the commencement of next work.
5. The contractor shall arrange for all compliance to the ESI/PF rules in force. Cattle Feed Plant shall not be liable for any benefits/compensation to the workers engaged by the contractor, in the event of accidents/mishaps etc. during execution of work. The contractor shall provide suitable safety measures to their workmen at the work spot inside our plant. The contractor or his workmen shall not interfere in any activity of the Plant and/or cause any damages to buildings/property. The entry of all such workmen will be on the basis of gate pass, which will have to be arranged by the Contractor prior to starting the work. In the event of any damage to Milma Cattle Feed Plant's property, due to the Contractor, the Contractor alone shall be liable.
6. Statutory deductions related to Income tax, ESI, EPF and other applicable statutory deductions will be effected while settling bills.
7. The plant day to day activities shall not be affected during the course of work.
8. The work found inferior in quality/bad workmanship shall be redone at contractor's risk and cost.

SPECIFIC TERMS & CONDITIONS:

1. The Contractor shall provide all the materials required for the works. The Contractor shall supply tools and tackles required for the works. Nothing will be arranged from our end.
2. All prices must be quoted as for site basis. The price shall include labour charges, statutory deductions, all taxes and duties, freight, packing, forwarding transit risk, loading etc. for the safe delivery of the items required for the job order and nothing extra will be paid on this account at later stage for any reason.
3. The offer shall be valid for 2 months for acceptance from the date of your offer.
4. The entire works shall be completed within 15 days from the date receipt of the work order.
5. All the works shall be carried out as per the directions and supervision of our plant Engineer.
6. The Contractor shall guarantee to rectify defects if any noticed in works due to bad workmanship at free of cost.
7. All safety measures (like safety belts, scaffolding's etc.) related to the job order shall be arranged by the Contractor. Work permit shall be taken by the

Contractor before the commencement of work. All risk shall be covered by Contractor as per norms.

8. **Payment terms:** 100% payment will be released on satisfactory completion of scheduled supply & works.

Our bankers are: **SBI PALAKKAD / CANARA BANK MALAMPUZHA**

9. **Penalty Clause:** In the case of the assigned job order being not executed and completed within the stipulated time period of 15 days, a penalty @1% of the total quoted value will be deducted for every day of so delayed.
10. The undersigned reserves the right to accept your offer partly/or in full or to reject without giving any explanation.
11. The quotation notice is sent in duplicate copies (True & Duplicate copy). Kindly enter your price quote in the **ANNEXURE – 1** of true copy with office seal & signature. Duly filled in offer shall be submitted in a sealed cover with mentioning the Enquiry number of the Quotation Notice on it. The sealed quotation shall reach us on or before 2:00 PM of 17-05-2024 addressed to :
- MANAGER,
KERALA CO-OPERATIVE MILK MARKETING FEDERATION LIMITED,
MILMA CATTLE FEED PLANT, MALAMPUZHA, PALAKKAD – 678651

The offers should be sent in a sealed cover super scribed: **“SUPPLY CUM LAYING OF RS485 DATA CABLE ALONG WITH POWER CABLE AND FOR INSTALLING SILO RADAR LEVEL SENSOR”**

The quotations will be opened on 17-05-2024 @ 3.30 PM

MANAGER

Copy to: Finance Officer, Production Section, Office File & to be displayed at

1. All Notice Boards, CFPM
2. Canara Bank, Malampuzha
3. ITI, Malampuzha
4. Panchayath Office, Malampuzha
5. Milma website
6. Milma Palakkad Dairy, Kallepully

ANNEXURE – 1

FORMAT FOR QUOTATION SUBMISSION

Enquiry No: CFP-M/PRODN/150/2024-25/20/540/dated 06.05.2024

| | | |
|---|--|--|
| 1 | Name & Address of the Bidder | |
| 2 | Company Registration No: | |
| 3 | GST Registration No: (Enclose photocopy GST Registration Certificate) | |
| 6 | Aadhar/PAN: (Enclose photocopy of Aadhar/PAN also) | |
| 7 | Contact Details (Phone No. & email ID) | |

| Sl. No. | Description of items | Qty. | UOM | Unit Rate | Total Amount |
|----------------------------|---|----------------|-------|-----------|--------------|
| A. SUPPLY OF CABLES | | | | | |
| 1 | Supply of Data cable 1 PAIR X 1.00 SQMM SHIELED CABLE FOR RS485 COMMUNICATION | 125 x2 =250 | meter | | |
| 2 | Supply of Power cable 2 PAIR X 0.5 SQ MM SHIELED CABLE (1 PAIR FOR 24 V DC & 1 PAIR FOR 4 TO 20 MILLI AMPERE) | 125x2 =250 | meter | | |
| 3 | Supply of Reputed make ISI standard 20 mm PVC conduit with required no of bend, elbow, Tee and saddles, cable tie, nails etc. | 250 | meter | | |
| 4 | Supply of Reputed make ISI standard 25 mm GI pipe with necessary hardware etc. | 46 | meter | | |
| 5 | Supply of 4 inch x 4 inch GI / SS junction box with connector | 2 | Nos. | | |
| 6 | Supply of 6 inch x 6 inch GI / SS junction box with connector | 2 | Nos. | | |
| SUB -TOTAL | | | | | |
| GST | | | | | |
| TOTAL | | | | | |

| B. CHARGES FOR CABLE LAYING | | | | |
|--|---|--|------------------|---------------------|
| Sl. No. | Description of Works | Qty. | Unit Rate | Total Amount |
| 1 | Laying of 250 meter Data cable (1 PAIR X 1.00 SQMM SHIELEDDED CABLE FOR RS485 COMMUNICATION) through 20 mm PVC conduit | Cable laying inside 250 m of 20 mm PVC conduit | | |
| 2 | Laying of 250 meter Power cable (2 PAIR X 0.5 SQ MM SHIELEDDED CABLE(1 PAIR FOR 24 V DC AND 1 PAIR FOR 4 TO 20 MILLI AMPERE) through 20 mm PVC conduit | Cable laying inside 250 m of 20 mm PVC conduit | | |
| 3 | Laying Power and Data cables through 46 meter of 25 mm GI pipe with required no. of couplings, bends etc. after breaking the concrete road and again closing with re-plastering of the concrete road | Cable laying inside 46 m of 25 mm GI pipe | | |
| 4 | Laying of 2 nos. of 4 inch x 4 inch junction box with connector | 2 Nos. | | |
| 5 | Laying of 2 nos. of 6 inch x 6 inch junction box with connector | 2 Nos. | | |
| 6 | End termination and glanding of Power cable and Data cable (Including supply) - for 4 cable ends | 4 Nos. | | |
| | SUB-TOTAL | | | |
| | GST | | | |
| | TOTAL | | | |
| C. MOUNTING OF RADAR LEVEL SENSOR ON SILO ROOFTOP | | | | |
| Sl. No. | Description of Works | Qty. | Unit Rate | Total Amount |
| 1 | Make a 32 cm hole above the silo roofing sheet and mount 1 number of Radar Level Sensor (of approximately 15 kg weight) by securing with nuts and bolt, necessary stable mechanical supporting structures, water proofing packing of the sides etc. (required quantity of consumables for the same will be provided from plant) | 1 no. | | |
| | SUB -TOTAL | | | |
| | GST | | | |
| | TOTAL | | | |

Place:

Signature:

Date:

Name & Address:

Company Seal