



**KERALA CO-OPERATIVE MILK MARKETING
FEDERATION Ltd.**

**CENTRAL PRODUCTS DAIRY, PUNNAPRA P.O,
ALAPPUZHA**

No: CPD/ENGG/ELECTRICAL/2025-26

**TENDER FOR ELECTRICAL MAINTENANCE WORK IN
GHEE PACKING HALL AT CENTRAL PRODUCTS DAIRY,
PUNNAPRA P.O, ALAPPUZHA**



**KERALA CO-OPERATIVE MILK MARKETING FEDERATION LTD.
CENTRAL PRODUCTS DAIRY, PUNNAPRA P.O, ALAPPUZHA – 688 004.**

Tel: 0477-2255900, 2255999,2255921, E-mail: cpd@milma.com

GST:32AAAK5375M4ZD

No: CPD/ENGG/ELECTRICAL/2026-27

28/05/2026

Tender Notice

Kerala Co-operative Milk Marketing Federation Ltd., Central Products Dairy, Punnapra P.O, Alappuzha invites competitive quotations from experienced electrical contractors for the electrical maintenance works in ghee packing hall at Central Products Dairy, Punnapra P.O, Alappuzha subjected to terms & conditions stipulated.

1	Place of Submission of tender	Office of Milma Central Products Dairy, Punnapra P.O, Alappuzha -688 004
2	Tender Form Fee	Rs. 600/- (Rupees Six Hundred Only) as online remittance cash receipt at Central Products Dairy, Punnapra P.O, Alappuzha.
3	Earnest Money Deposit	Rs. 7500/- (Rupees Seven Thousand Five Hundred Only) as online remittance or cash receipt at Central Products Dairy Punnapra P.O, Alappuzha.
4	Last Date and time of submission of tender	Sealed quotations shall be submitted at Central Products Dairy Punnapra P.O, Alappuzha office on or before 12/06/2026, 1.00PM by hand/courier/post,along with the EMD details (transaction details).The envelope should be titled “ Electrical maintenance works in ghee packing hall at Central Products Dairy, Punnapra P.O, Alappuzha ”
5	Date and time of opening of tender	12/06/2026 , 3.30 PM
6	Venue of opening of tender	Office of Milma Central Products Dairy Punnapra P.O, Alappuzha-688 004

[BANK DETAILS: STATE BANK OF INDIA , KCMMF Ltd.,Punnapra,Alappuzha-4, IFSC CODE – SBIN0070215, ACCOUNT No. -67192090757]

For more details please contact in Ph. No: 9496115836, 9495967751, 9847350912 during office hours.

DAIRY MANAGER



**KERALA CO-OPERATIVE MILK MARKETING FEDERATION LTD.
CENTRAL PRODUCTS DAIRY, PUNNAPRA P.O, ALAPPUZHA – 688 004.**

Tel: 0477-2255900, 2255999,2255921, E-mail: cpd@milma.com

GST:32AAAAK5375M4ZD

No: CPD/ENGG/ELECTRICAL/2026-27

28/05/2026

Kerala Co-operative Milk Marketing Federation Ltd., Central Products Dairy, Punnapra P.O, Alappuzha invites competitive quotations from experienced electrical contractors for the electrical maintenance works in ghee packing hall at Central Products Dairy, Punnapra P.O, Alappuzha subject to the following terms and conditions.

1. SCOPE OF WORK:

The scope of work includes supply, erection, testing and commissioning of electrical DBs, cables, conduit wiring etc required for the electrical modification works inside ghee packing hall.

2. TERMS AND CONDITIONS:

1. The rate quoted shall be inclusive of all applicable taxes and duties, ESI contribution, material cost, labour cost, transportation of materials to site, loading and unloading charges and nothing extra will be paid on any account.
2. The unit rates should be quoted both in figures as well as in words. In case of discrepancy in the rate quoted in figures as well as in words, the amount quoted in words shall be taken as final and binding on the party.
3. Based on the unit rates quoted, the total amount for work should be worked out and indicated in the offer. The unit rate quoted should be legible without any erasion /overwriting. In case of any correction and alterations in the unit rates at the time of quoting the same should be signed in full by the quotationer.
4. Quantities indicated in the schedule are only tentative and may vary to the +/- side.
5. **The bidder shall quote the rates in the Annexure-1 attached with the tender document only. The bids shall be submitted after signing at the bottom of every page of tender document.**

3. VALIDITY:

The offers submitted by the quotationer shall remain valid for acceptance for a period of 60 days from the date of opening.

4. PERIOD OF COMPLETION:

At the items specified in the scope of order should be completed in all respects within 30 days from the date of receipt of work order. However, the quotationer after examining the scope of work and site conditions can specify in the offer the shortest period by which he will complete the works in all respects.

5. SUBMISSION OF BILLS AND PAYMENT:

1. Bills shall be prepared in duplicate in the name of the **Kerala Co-Operative Milk Marketing Federation Ltd, Central Products Dairy, Punnapra P.O, Alappuzha GST: 32AAAAK5375M4ZD** and shall be submitted along with the copy of the GST registration, PAN card to the Engineer for necessary certification and recommendation for payment.

2. 90% Payment will be released within 15 days after completion of work in all respects.
3. Balance 10% of contract amount will be released after successful completion of guarantee period of one year from the date of completion of work.

6. EARNEST MONEY DEPOSIT:

1. The quotations should be accompanied by an EMD of Rs. 7,500/-(Rupees Seven Thousand Five Hundred Only).
2. The EMD shall be in the form of online remittance or cash receipt at Central Products Dairy Punnapra P.O, Alappuzha in dairy accounts section.
3. Offers without EMD are liable to be rejected.
4. The EMD of the unsuccessful quotationer's will be released on finalization of the contract. The EMD of the successful quotationer will be released only after satisfactory completion of the work in all respects. No interest will be paid for the EMD for the period for which it lies with the unit.

7. SUBMISSION OF QUOTATIONS AND OPENING:

1. The offer must be submitted in original in a sealed cover super scribed the name of the work, due date and time of opening.
2. **Bidder should attach this tender document with rates written in the annexure attached along with this tender document, after signing at the bottom of each page of tender document as a token of acceptance of the terms and conditions and specification.**
3. The bank account detail of dairy is shown below for online remittance of tender fee and EMD.

Bank	State Bank of India
Account Name	KCMMF Limited
Branch	Punnapra, Alappuzha-4
IFSC Code	SBIN0070215
Account No	67192090757

4. The offers complete in all respects should reach this office on or before 1 PM on 12/06/2026 and the same shall be opened at 3.30 PM on 12/06/2026 in the presence of interested quotationer or their authorized representatives.
5. The bids received after the tender submission date and time will not be accepted. Dairy will not be responsible for any delay in receiving the bids sent through post/courier.

8. GUARANTEE:

1. The Contractor will guarantee to repair / replace without any extra cost of the work carried out in part or full if found defective due to bad workmanship or substandard materials within 12 months from the date of handing over the project duly completed in all respects. The entire expenditure towards replacement / repair shall be borne by the contractor.

9. GENERAL:

1. The materials required for the above work shall have to be arranged by the contractor at site without any hindrance to the daily operation of the Dairy.
2. The work should be carried out in consultation with the Engineer or the authorized representative of the undersigned and should be strictly as per the specification and requirement.
3. The work on completion should be fulfilled required statutory norms fixed and if necessary the contractor should fulfill the same.

4. Contractor shall provide sufficient work force in the nature of skilled / semiskilled / unskilled workers for the execution of work under the contract and shall take all safety precautions and follow the safety regulations of KCMMF LTD as per Factories Act.
5. The undersigned reserves the right to accept any quotation in part or full.
6. The undersigned reserves the right to accept or reject any or all quotations without assigning any reason whatsoever and no explanation can be sought on this account.
7. The work will be allotted to the successful quotationer only on prior approval by the Managing Director, KCMMF LTD.

DAIRY MANAGER
CENTRAL PRODUCTS DAIRY

Annexure-I

To,

**The Dairy Manager
KCMMF Ltd.,
CENTRAL PRODUCTS DAIRY,
PUNNAPRA P.O, ALAPPUZHA – 688 004.**

Dear Sir,

**Sub: - Electrical maintenance works in ghee packing hall at Central Products Dairy,
Punnapra P.O, Alappuzha - reg.**

Having examined the General conditions/Instructions to the contractors, Scope of supply, Special terms and conditions, Bill of Quantities, Technical specifications relating items specified in the tender hereinafter set out and having visited and examined the site of works specified in the said tender and having acquired the requisite information relating thereto as affecting the tender. I/We hereby offer to execute the supply of items specified in the tender in accordance with the rates mentioned in the below schedule in all respects with the specification and instructions with writing and with such materials as are provided for in all other respects in accordance with such conditions so far as they may be applicable.

SCHEDULE OF ITEMS FOR SUPPLY

Sl. No	Description	Unit	Qty	Unit Rate - Supply Including all	Unit Rate - Labour Including all	Total Amount - Supply Including all	Total Amount - Labour Including all
1	S/F Vertical TPN MCB DB : Supply, installation testing and commissioning of 8 way, three pole and neutral sheet steel vertical type distribution board, 415 volts on surface /concealed complete with tinned copper busbar, neutral link, earth bar, dinbar, detachable gland plate, mcb dummy inter connections, double door, phosphatized and powder painted including required fittings, earthing etc as required (without MCB/RCCB/ Isolator)	Nos	1				
2	S/F Horizontal SPN Prewired MCB DB : Supply, installation testing and commissioning of 12 way, single pole and neutral sheet steel prewired distribution board, 230 volts on surface /concealed complete with tinned copper busbar, neutral link, earth bar,	Nos	3				

	dinbar, detachable gland plate, mcb dummy, inter connections, double door, phosphatized and powder painted including required fittings, earthing etc as required(without MCB/RCCB/ Isolator)						
3	S/F Horizontal SPN Prewired MCB DB : Supply, installation testing and commissioning of 16 way, single pole and neutral sheet steel prewired distribution board, 230 volts on surface /concealed complete with tinned copper busbar, neutral link, earth bar, dinbar, detachable gland plate, mcb dummy, inter connections, double door, phosphatized and powder painted including required fittings, earthing etc as required (without MCB/RCCB/ Isolator)	Nos	1				
4	Supply and fixing of 20A TP+N, 3P+N+E metallic socket with cover and plug top fitted in a suitable metallic enclosure controlled by 20A FP MCB with neutral link and inter connections etc complete. As per IEC 61439-3	Nos	3				
5	Supply and fixing of 32A SP, 2P+E metallic socket with cover and plug top fitted in a suitable metallic enclosure controlled by 20A SP MCB with neutral link and inter connections etc complete. As per IEC 61439-3	Nos	3				
6	S/F TPN RCCB : Supply, installation testing and commissioning the 40A 30mA FP RCCB rating, 415 volts triple pole & neutral Residual Current Circuit Breaker (RCCB) having sensitivity current capacity of 30mA in the existing MCB DB complete with connections etc as required. RCCB shall be same make as DB quoted.	Nos	1				
7	S/F TPN RCCB : Supply, installation testing and commissioning the 63A 30mA FP	Nos	1				

	RCCB rating, 415 volts triple pole & neutral Recidual Current Circuit Breaker (RCCB) having sensivity current capacity of 30mA in the existing MCB DB complete with connections etc as required. RCCB shall be same make as DB quoted.						
8	S/F TPN RCCB : Supply, installation testing and commsisiong the 100A 100mA FP RCCB rating, 415 volts triple pole & neutral Recidual Current Circuit Breaker (RCCB) having sensivity current capacity of 100mA in the existing MCB DB complete with connections etc as required. RCCB shall be same make as DB quoted.	Nos	1				
9	S/F SPN RCCB : Supply, installation testing and commsisiong the 63 A rating, 230 volts single pole & neutral Residual Current Circuit Breaker (RCCB) having sensivity current capacity of 300mA in the existing MCB DB complete with connections testing and commissioning etc as required. RCCB shall be same make as DB quoted.	Nos	1				
10	S/F SPN RCCB : Supply, installation testing and commsisiong the 40 A rating, 230 volts single pole & neutral Residual Current Circuit Breaker (RCCB) having sensivity current capacity of 300mA in the existing MCB DB complete with connections testing and commissioning etc as required. RCCB shall be same make as DB quoted.	Nos	1				
11	S/F 'C' Series, MCB : Supply, installation testing and commsisiong 32 amps rating 240/415 volts C series miniature circuit breaker suitable for lighting and other loads of the 3	Nos	6				

	poles in the existing MCB DB complete with connections testing and commissioning etc as required.MCB shall be same make as the DB quoted.						
12	S/F 'C' Series, MCB : Supply, installation testing and commsisiong 40 amps rating 240/415 volts C series miniature circuit breaker suitable for lighting and other loads of the 3 poles in the existing MCB DB complete with connections testing and commissioning etc as required.MCB shall be same make as the DB quoted.	Nos	2				
13	S/F 'C' Series, MCB : Supply, installation testing and commsisiong 40 amps rating 240/415 volts C series miniature circuit breaker suitable for lighting and other loads of the 4 poles in the existing MCB DB complete with connections testing and commissioning etc as required.MCB shall be same make as the DB quoted.	Nos	1				
14	S/F 'C' Series, MCB : Supply, installation testing and commsisiong 63 amps rating 240/415 volts C series miniature circuit breaker suitable for lighting and other loads of the 4 poles in the existing MCB DB complete with connections testing and commissioning etc as required.MCB shall be same make as the DB quoted.	Nos	1				
15	S/F 'C' Series, MCB : Supply, installation testing and commsisiong 100 amps rating 240/415 volts C series miniature circuit breaker suitable for lighting and other loads of the 4 poles in the existing MCB DB complete with connections testing and commissioning etc as required.MCB shall be same make as the DB quoted.	Nos	1				
16	S/F 'C' Series, MCB : Supply,	Nos	1				

	installation testing and commissioning 40 amps rating 240/415 volts C series miniature circuit breaker suitable for lighting and other loads of the double poles in the existing MCB DB complete with connections testing and commissioning etc as required.MCB shall be same make as the DB quoted.						
17	S/F 'C' Series, MCB : Supply, installation testing and commissioning 63 amps rating 240/415 volts C series miniature circuit breaker suitable for lighting and other loads of the double poles in the existing MCB DB complete with connections testing and commissioning etc as required.MCB shall be same make as the DB quoted.	Nos	1				
18	S/F 'C' Series, MCB : Supply, installation testing and commissioning 6 amps rating 240/415 volts C series miniature circuit breaker suitable for lighting and other loads of the single poles in the existing MCB DB complete with connections testing and commissioning etc as required.MCB shall be same make as the DB quoted.	Nos	10				
19	S/F 'C' Series, MCB : Supply, installation testing and commissioning 10 amps rating 240/415 volts C series miniature circuit breaker suitable for lighting and other loads of the single poles in the existing MCB DB complete with connections testing and commissioning etc as required.MCB shall be same make as the DB quoted.	Nos	10				
20	S/F 'C' Series, MCB : Supply, installation testing and commissioning 16 amps rating 240/415 volts C series miniature circuit breaker suitable for lighting and other loads of the single poles in the existing MCB	Nos	10				

	DB complete with connections testing and commissioning etc as required.MCB shall be same make as the DB quoted.						
21	S/F 'C' Series, MCB : Supply, installation testing and commsisiong 32 amps rating 240/415 volts C series miniature circuit breaker suitable for lighting and other loads of the single poles in the existing MCB DB complete with connections testing and commissioning etc as required.MCB shall be same make as the DB quoted.	Nos	6				
22	Supply, Laying, testing and commissioning of 2 X 10 sqmm sizes of 1.1KV XLPE insulated, PVC sheathed Copper conductor UG Cable including supply and fixing of clamping materials.	Met er	130				
23	Supply, Laying, testing and commissioning of 4 X 6 sqmm sizes of 1.1KV XLPE insulated, PVC sheathed Copper conductor UG Cable including supply and fixing of clamping materials.	Met er	75				
24	Supply and providing indoor end termination of 2 X 10 Sqmm sizes of 1.1KV XLPE insulated, PVC sheathed Al conductor (A2XFY) UG Cable including supply of necessary steel glands, Aluminium lugs and gland earthing by copper shim etc complete.	Set	6				
25	Supply and providing indoor end termination of 4 X 6 Sqmm sizes of 1.1KV XLPE insulated, PVC sheathed Al conductor (A2XFY) UG Cable including supply of necessary steel glands, Aluminium lugs and gland earthing by copper shim etc complete.	Set	6				
26	POINT WIRING: Supply and carrying out wiring for lights, fans, and plug points including testing and commissioing in concealed conduit system from	Poin t	32				

	control board to the respective points. Wiring is to be done by using single core PVC insulated stranded 1.1 kV grade class2 FRLSH copper wire size of 1.5sqmm along with same size wire as earth continuity conductor through rigid 25mm PVC ISI grade conduit (Heavy duty) with necessary bends, Junction boxes, saddles, ceiling roses/angle batten and modular type 6A switches, on switch boards etc complete One Light Point Controlled by one number 6A Switch. (The point length limited to 10 mtrs and looping 3 Mtr).							
27	Supply and carrying out wiring in concealed conduit system from DBs to switch boards using (3 runs X 1.5 sqmm) of single core PVC insulated 1.1 kV grade Class 2 copper wire FRLSH through 25mm PVC ISI grade conduit (Heavy duty) with necessary bends, Junction boxes, saddles including giving connections etc complete.	Met er	130					
28	Supply of 10SWG sizes of copper wires for earthing of motors, isolators, push button stations, switchboards, motor control centers, distribution Boards etc. as per technical Specification. Rate shall be inclusive of necessary tinning, providing sockets and end termination of copper strips/wires with all accessories required for the completion of work.	Met er	150					
Total								
Total Amount (Supply + Labour) including all								

Total Amount in words:

The rate quoted shall be inclusive of all applicable taxes and duties, packing cost, transportation of materials to dairy, loading and unloading. Nothing extra will be paid on any account.

Certified that I have read the terms and conditions of the Tender Notice No: CPD/ENGG/FLOOR CLEANING MACHINE/2026-27 dated 28/05/2026 and agree to the same.

<u>Name & Address of the Bidder</u>	
Phone No: with STD Code	
Mobile Phone No:	
Date of Submission of Tender	

Signature of the Bidder: