milma

KERALA CO-OPERATIVE MILK MARKETING FEDERATION LTD
CATTLE FEED PLANT, MALAMPUZHA (PO), PALAKKAD – 678651
Tel: 0491-2816317, 2816316, 2816301 E mail: cfmprod@milma.com

Re-tender Notice for Construction of Maintenance Working Platforms and Miscellaneous Structural Works inside Milma Cattle Feed Plant, Malampuzha

Quotation Notice No: CFPM/PROD/107/MIS/2026-27/4542
Dated: 06-11-2026

Kerala Co-Operative Milk Marketing Federation Limited (MILMA), Cattle Feed Plant, Malampuzha, Palakkad - 678651 Re-invites your sealed competitive price quotations for **Construction of Maintenance Working Platforms and Miscellaneous Structural Works** as per the scope of works enlisted in the **Annexure** enclosed herewith. The bidding shall be subjected and binding to the following terms and conditions.

I. General Terms & Conditions:

1. PRICE BASIS: All prices must be quoted as FOR site basis, including all taxes cum duties and freight, packing, forwarding, transit risk insurance, loading, unloading, miscellaneous incidental charges for the safe delivery of the items at our end and labour charges for the entire construction. Nothing extra will be paid on this account for any reason.

2. PRICE VALIDITY: The competitive price offered shall remain valid for 3 months for acceptance from the date of your offer. Once you have secured the contract for the amount you quoted no price deviation/dynamic pricing is allowed until the works as per the contract is completed.

3. GUARANTEE PERIOD: The contractor must guarantee for performance and the quality of the constructed structure for a minimum period of one year. The contractor shall rectify defects if any noticed in works due to bad workmanship at free of cost during the guarantee period.

4. PAYMENT MODE: 90% of the payment will be released against the invoice within 30 days after satisfactory completion of the entire job, and the remaining 10% will be released after the guarantee period. Advance payment will not be entertained. Our bankers are SBI, Palakkad, and Canara Bank, Malampuzha.

5. EMD: The bidders shall furnish an Earnest Money Deposit (EMD) of ₹3,100/- along with their bids. The EMD shall remain valid for a period of 45 days beyond the final tender validity period. The EMD shall be liable to forfeiture if the bidder withdraws, amends or otherwise modifies or derogates from the terms of the tender in any respect during the tender validity period. The EMD furnished by unsuccessful bidders shall be refunded without any interest at the earliest after the expiry of the final tender validity period, but not later than 30 days after the conclusion of the contract. The EMD amount may be remitted directly at the Factory Finance Department, subject to obtaining proper recommendation from the concerned Production Section Officers.

6.Document Fee : A document fee of ₹118/- (inclusive of GST) shall be applicable. Interested vendors shall remit the amount at the Factory Finance Department and collect the quotation notice from the Production Section upon payment.

7. LIQUIDATED DAMAGES

CLAUSE: In case the work is not completed within the stipulated time period, liquidated damages @1% of total work order value per week will be charged for the items so delayed subject to a maximum of 5% of the total value. Later the contract work order may be cancelled with the discretion of KCMMF

II. Specific Terms & Conditions:

1. **Essential Documents:** The bidder shall furnish the following details/documents (as copy) for becoming eligible to technically qualify in the bid
    a. Name of the Bidder / Enterprise entitled to supply
    b. Company Registration certificate
    c. Address proof of the Enterprise
    d. Valid ID proof of the Bidder (such as Adhar)
    e. PAN copy
    f. GST registration certificate copy (if registered)
    g. ESI Certificate if enrolled
    h. Previously executed work orders/contract completion certificate (if any available as proof of work experience)
2. All the works shall be carried out as per the directions and supervision of our plant Engineer.
3. The Contractor shall provide all the materials required for the worksite before commencement of work. The Contractor shall supply tools and tackles required for the works with necessary documents. Nothing will be arranged from our end.
4. The contractor shall arrange for all compliance to the ESI/PF rules in force. Cattle Feed Plant shall not be liable for any benefits/compensation to the

workers engaged by the contractor, in the event of accidents/mishaps etc. during execution of work. The contractor shall provide suitable safety measures to their workmen at the work spot. The contractor or his workmen shall not interfere in any activity of the Plant and/or cause any damages to buildings/property. The entry of all such workmen will be on the basis of gate pass, which will have to be arranged by the Contractor prior to starting the work. In the event of any damage to Milma Cattle Feed Plant's property, due to the Contractor, the Contractor alone shall be liable.

5. Statutory deductions related to Income tax, ESI, EPF and other applicable statutory deductions will be effected while settling bills.
6. The entire works shall be completed within 45 days from the date receipt of the work order.
7. All safety measures (like safety belts, scaffolding's etc.) related to the job order shall be arranged by the Contractor. Work permit shall be taken by the Contractor before the commencement of work. All risk shall be covered by Contractor as per norms, KCMMF has no liabilities in this regards.
8. The supply order materials shall be inspected by our Engineers before acceptance for the said work. The materials shall be of our approved make as per the schedule of work order.
9. Any deviations in the price quote, validity period, guarantee period, payment mode from as stipulated above shall be clearly specified in the bid itself.
10. Rates shall be quoted only in Indian Rupees. Rates shall be fixed during the entire validity period and Price quotations with dynamic pricing and including any other conditional clauses will be summarily rejected.
11. **Right of Acceptance:** The undersigned reserves the right to accept the offer either in full or in part, or to reject it entirely, without assigning any reason.
12. **Bid Opening:** Only sealed quotations received by postal are valid and considered for evaluation. Open quotations submitted in hand or sent by email will be treated non-responsive and will be totally rejected. Hence the bidders are requested to send their valuable sealed quotations by postal well in advance before the date of opening. Sealed quotations shall reach our office on or before **3:00 PM of 20.11.2026** and the received quotations will be opened on the same day at **3.30 PM** in the presence of bidders if any available. Quotations received after **3:00 PM** will be rejected.
13. **Bidder Confirmation:** Technically qualified bids will only be considered for financial evaluation. Price bids will be assessed in accordance with the Least Cost Based Selection System. All the bids will be evaluated on the basis of the eligibility criteria through verification of all the essential documents submitted along with the terms & conditions complied by bidder. Though the L1 bidder will be the preferred bidder, simply quoting of lowest rate does not confer any right for selection of the bidder at the rate quoted. KCMMF reserves the right to confirm and finalize the bidder. Quoting of same rates (L1 only) by more than one bidder could be construed as an exceptional circumstance. In such cases, all the bidders who have quoted the same lowest rates shall be called for and one more chance will be given for on spot quoting if bidders are present or negotiated quote may be collected via mail with a closing time for rate finalization. If the negotiated quotes are still the same, KCMMF reserves the right to award the work order based on the level of experience of the bidder or may proceed with re-tender at its discretion.
14. **Experience**: The bidder shall possess required experience for a minimum period of three years at the time of bid opening.

15. **Details of Scope of Works**: Detailed scope of works with specifications and quantity are as mentioned in the Annexure enclosed herewith and also available at our official website https://www.milma.com/tender/tendernotices

16. **Bid Submission Details:**
The quotation must be submitted in a sealed cover clearly super scribed: **"Construction of Maintenance Working Platforms and Miscellaneous Structural Works"– Due on 20.11.2026**"and shall be addressed to:

THE MANAGER
KCMMF LIMITED
MILMA CATTLE FEED PLANT
MALAMPUZHA
PALAKKAD – 678651

17. Interested bidders may visit the site & communicate with our officials through the phone numbers mentioned above on all working days between 9 AM to 5 PM with prior intimation, before bid submission.

MANAGER

K.C.M.M.F.LTD. MALAMPUZHA CATTLE FEED PLANT

Copy to: FO, HOD-P&M, Office File

To be displayed/published at

1. **All Notice Boards, CFPM**
2. **Panchayath Office, Malampuzha**
3. **ITI, Manthakkad**
4. **Village Office, Malampuzha**
5. **Milma website**
6. **Milma Dairy, Palakkad**

Encl: Annexure (Detailed scope of Works with specifications & quantity)

milma

KERALA CO-OPERATIVE MILK MARKETING FEDERATION LTD
CATTLE FEED PLANT, MALAMPUZHA (PO), PALAKKAD – 678651
Tel: 0491-2816317, 2816316, 2816301 E mail: cfmprod@milma.com

Notice inviting tender for Construction of Maintenance Working Platforms and Miscellaneous Structural Works inside Milma Cattle Feed Plant, Malampuzha

Quotation Notice No: CFPM/PROD/107/MIS/2026-27/ Dated: 06-11-2026

TECHNICAL BID SUBMISSION FORMAT

Sl. No.	Description	Details
1	Name & Address of the Bidder	
2	Phone Number (Mob)/ Land Line, E mail ID	
3	Aadhaar Card Number (linked with PAN): (Documents to be enclosed)	
4	GST Registration Number (Documents to be enclosed)	
5	PAN card Registration Number (Documents to be enclosed)	
6	EMD Receipt Ref.	

Date: Name of Bidder/Enterprise:

Seal & Sign: Address:

ANNEXURE
(Price Bid Submission Format)

TECHNICAL SPECIFICATION – STRUCTURAL STEEL PLATFORM WORKS

Providing all materials, structural steel sections, hollow structural sections, MS chequered plates, fasteners, welding electrodes, consumables, labour, tools, tackles, lifting equipment, scaffolding, safety arrangements, transportation, loading, unloading, fabrication, erection, alignment, testing, and commissioning required for the complete execution of the structural platform works.

The work shall include the following:

1. Supply, fabrication, and erection of maintenance platforms, access platforms, ladders, handrails, support frames, brackets, and all associated structural members using MS tubular sections, angles, channels, plates, flats, and chequered plates of approved quality conforming to relevant IS standards.
2. Cutting, drilling, edge preparation, grinding, welding, fitting, bolting, anchoring, levelling, plumbing, alignment, and fixing of structural members complete in position as per site requirements and as directed by the Engineer-in-Charge.
3. Fabrication shall be carried out using standard engineering practices. All welded joints shall be continuous, properly dressed, free from cracks, slag inclusions, undercuts, or other defects. Sharp edges and weld spatters shall be removed before painting.
4. Necessary anchor fasteners, foundation bolts, expansion anchors, base plates, cleats, gusset plates, stiffeners, brackets, special-shaped washers, nuts, bolts, locking arrangements, and all miscellaneous fittings required for complete installation shall be included in the quoted rate.
5. All fabricated steel surfaces shall be thoroughly cleaned by mechanical wire brushing/grinding to remove rust, mill scale, oil, grease, welding slag, and loose particles before application of protective coatings.
6. Corrosion protection shall consist of:
    - Two coats of epoxy zinc phosphate primer (minimum 50 microns DFT per coat); and
    - Two coats of epoxy finish paint (minimum 40 microns DFT per coat), applied to achieve a total dry film thickness of not less than 180 microns, including touch-up painting after erection.
7. **The contractor shall take all site measurements before fabrication. Quantities indicated in the schedule are approximate and intended only for guidance. The contractor shall verify all dimensions at site before commencement of submitting quotation, and no additional payment shall be made for variations arising from actual site conditions.**
8. The contractor shall provide all temporary supports, staging, scaffolding, lifting arrangements, and safety measures necessary for execution of the work inside the operating plant without affecting normal production.
9. Any cutting, shifting, modification, or strengthening required during erection for proper installation shall be deemed included in the quoted rate unless specifically excluded in writing.

10. All works shall conform to relevant Indian Standards, good engineering practice, applicable safety regulations, and the directions of the Engineer-in-Charge.
11. The quoted rate shall be deemed to include all materials, labour, fabrication, transportation, erection, welding, fastening, painting, testing, commissioning, wastage, overheads, statutory compliances, and incidental works necessary for the satisfactory completion of the job.

Measurement:
The work shall be measured and paid on a Lump Sum (LS) basis for the complete execution of each item described in the schedule, irrespective of minor variations in individual member quantities required for satisfactory completion.

Sl. No.	Description	Unit	Qty	Rate (Rs.)	Amount (Rs.)
	Structural Steel Works: Providing all materials, labour, tools, plant, equipment, and consumables for fabricating and erecting built-up steel work using tubular sections (round, square, or rectangular hollow tubes, etc.), including cutting, drilling, welding, hoisting, aligning, and fixing in position with bolts, nuts, and special-shaped washers, as required. The work shall also include the application of two coats of epoxy primer followed by two coats of epoxy paint to all exposed steel surfaces, complete in all respects, in accordance with the specifications and as directed by the Engineer-in-Charge. **Note: The approximate material requirements for the following works are indicated for reference only and may vary depending on the actual site conditions and execution requirements. The contractor visit the factory before quoting for taking the exact measurement and shall execute the work as directed by the Engineer-in-Charge.**				

1	**Boiler Platform Work (2 Sets) –** Fabrication, supply, erection, welding, bolting, painting and commissioning of Boiler Maintenance Working Platforms (2 Sets) complete with structural members, chequered plates, handrails, ladders, supports, anchor fasteners and all accessories required for complete installation. **Approximate Schedule of quantities:** 65mm Round pipe post (2 1/2") 12 feet - 4 Nos. 80x40 - 36 meter Checkerplate 8x4 (4mm thick) - 2 Nos. Hand rail 40x40 - 18 meter Ladder 32x32 Square tube - 6 mtr Holl plate 6x6 type - 8 Nos Hanger bolt 10mm - 20 Nos.	Lumpsum	1		
2	**Working platforms for Pellet elevator top portion (near pellet sieve)** Fabrication and erection of Working Platform at Pellet Elevator Top Portion (Near Pellet Sieve) including chequered plate flooring, structural frame, handrails, supports, welding, painting and all incidental works. **Approximate Schedule of quantities:** Checker plate 8x4 - 1 Nos. 40x6 Angles - 9 mtr Hand rail 40x40 - 18 mtr	Lumpsum	1		
3	**Modification of Existing Working Platform at Maize Elevator Jute Area** including structural alterations, additional steel members, chequered plates, welding, cutting, finishing and painting. **Approximate Schedule of quantities:** 40x6 angles-3 mtr -1 Nos & Required checker plates	Lumpsum	1		
4	Fabrication and erection of **Working Platform at Maize Road Cross Conveyor** including platform, ladder, side protection, structural frame, supports, painting and all accessories. **Approximate Schedule of quantities:** Frame size: 5x3 type 1	Lumpsum	1		

	40x40 – 9 mtr 50x25 Tube - 3 mtr				
5	**Working platform at 18 BIN Distribution conveyors area (DC1 & DC3)** Fabrication and erection of Working Platforms at BIN-18 Distribution Conveyor Area (DC-1 & DC-3) complete with chequered plates, structural frame, handrails, supports, welding and painting **Approximate Schedule of quantities:** Checker plate:1370X1200-1Nos & 1600X1300-1 Nos, 60x40 tube-15 mtrs, Checker plates- 4 ½" x 4" -1 nos, 5 feet 3 inchx4 ¼" -1 nos, Handrail 32x32 tube-18 mtrs	Lumpsum	1		
6	**Outside working platform at Air lock discharge pipe** Fabrication and erection of Outside Working Platform at Air Lock Discharge Pipe complete with supporting structure, chequered plates, flooring, roofing, Door, handrails, ladder, painting and accessories. **Approximate Schedule of quantities:** Checker plate: 1980x900 6 1/2 Length, width-3 feet Platform Frame: 80x40 tubes Support: 12 ½ mtr pipe Roof Size: Length-2100 & width-1500 Pipe Size: 40x40 tube-8 mtr, 50x25 tube-2 mtr, Supports 80x40 tube-4 mtrs Handrail:32x32 square tube-12 mtrs	Lumpsum	1		
7	**Roofing Modification at Bypass Plant Elevator Top** including supporting steel structure, color coated roofing sheets, side cladding, fasteners, fabrication, erection and painting. **Approximate Schedule of quantities:** 32x32 Tube - 30 meter 60x40 Tube - 9 meter Self bolt - 200 Nos. Roof sheet 14 type - 1 Nos	Lumpsum	1		

8	Fabrication and erection of **Working Platform at Bypro Elevator Top Area** complete with structural frame, chequered plate flooring, posts, handrails, ladder, welding and painting. **Approximate Schedule of quantities:** Checker plate 8x4 - 1 Nos & 4x4 - 1 Nos. Post 8 feet. Side Handrail 40x40 - 21 Meter	Lumpsum	1		
9	**Modification Works for Mix Feed Conveyor Maintenance Access** including fabrication, installation of access plates, supports, welding, painting and all incidental works. **Approximate Schedule of quantities:** 4mm THK 500x500 plate - 1 Nos. 600x300 plate – 1nos	Lumpsum	1		
10	**Working platform for Maize two way flap near molasses tank** Fabrication and erection of Working Platforms with chequered plates, structural frame, handrails, supports, welding and painting **Approximate Schedule of quantities:** Outer frame: 50x6mm Angle-12 mtrs 40x6 angle-12 mtrs Checker plates: 8x4 (4 mm thick)-1 nos & 6x4 (4 mm thick)-1 nos Handrails:32x32 square tube-18 mtr	Lumpsum	1		
Total Value without GST (Rs.)					
GST @ .....% (If applicable)					
Total Value (incl. all)					

Date: Name of Bidder/Enterprise:

Seal: Address:

Signature: