



**KERALA CO-OPERATIVE MILK MARKETING FEDERATION LTD.**  
**CATTLE FEED PLANT, PATTANAKKAD P.O, ALAPPUZHA – PIN 688 531**  
**Tel: 0478-2831100, 2831122, 2831112-124, E-mail: cfp@milma.com**  
**GST NO32AAAK5375M1ZG**

**NO.CFPT/PE/555/2025-26/482**

**22/09/2025**

**Sub:-Enquiry for dismantling of damaged corrugated sheets and installation of new corrugated sheets at grain silo (maize) at cattle Feed Plant, Pattanakad.**

Quotations are invited from professionals for the replacement of damaged corrugated sheets at grain silo for maize at our Cattle Feed Plant Pattanakad.

**Scope of work**

The scope of work includes the supply of all necessary labour, tools, tackles, and consumable materials such as beading, silicone, and other items required to complete the job. It involves the dismantling and removal of damaged corrugated sheets from the grain silo, followed by installation of new corrugated sheets which is supplied by milma. The grain silo has a diameter of 9095 mm and a shell height of 12650 mm. Damaged shell are at an approximate height of 8m from the ground level. Expected sheets to be replaced are to be a maximum of 2-3 sheets. Rate quoted must be based on per sheet replacement basis. Upon completion of the installation, a water leakage test shall be conducted to ensure the integrity and water tightness of the structure. All activities are to be carried out in compliance with applicable safety and quality standards.

**PRICE**

Prices and charges quoted shall be firm and fixed during the entire period of contract and shall not be subject to any variation or escalation whatsoever on any account. The prices quoted shall be for Cattle Feed Plant, Pattanakad, Alappuzha, including all taxes and duties, insurance charges, GST etc. at site

**General Conditions**

1. Interested contractors are requested to visit the site during working days from 10AM to 4PM before posting the quotation.
2. All materials like scaffolding, ladder, tools, tackles, safety belts, PPEs etc. required are to be arranged by the contractor and all safety measures required for the workers engaged shall be taken care of by the contractor.
3. All necessary GI bolts and nuts (fasteners of same type) required for the replacement work are to be provided by the contractor and consumables like beadings, silicon etc. brought in shall be of approved makes.
4. New corrugated sheets will be supplied by Milma.
5. Water leakage test should be conducted after completion of work by the contractor under the supervision of Milma Representative.
6. The entire work shall be completed within 15 days from the date of receipt of the work order.
7. Work found inferior in quality/workmanship on completion shall be redone at contractor's risk and cost.
8. The contractor shall guarantee to rectify any defect on this work undertaken due to bad workmanship or usage of substandard materials, within six months from the date of completion of the work. An undertaking shall be submitted along with the bill for payment.
9. Each item of work shall be approved prior to commencement of the next work.

10. The contractor will be permitted to carry out the work only after the receipt of work permit issued by our Maintenance Engineer. The validity of the permit is one day only; if the work is not completed within a day a fresh permit shall be taken on next day.
11. The contractor shall arrange for all compliance to the ESI/PF rules in force. Cattle Feed Plant shall not be liable for any benefits/compensation to the workers engaged by the contractor, in the event of accidents/mishaps etc. during execution of work. The contractor shall provide suitable safety measures to Workers.
12. The contractor or his workmen shall not interfere in any activity of the Plant and/or cause any damages to buildings/property. The entry of all such laborers will be on the basis of gate pass, which will have to be arranged by the Contractor prior to starting the work. In the event of any damage to Cattle Feed Plant's property, the contractor alone shall be liable.
13. Income tax, work contract tax, ESI on the labour part and other applicable statutory deductions if any shall be effected while settling bills.
14. All the safety measures must be taken by the contractor against the potential hazards like pinch points, electric shock, falling objects and work at height etc.
15. 100% payment will be released after satisfactory completion of the entire works and submission of bills.

**The sealed quotation shall reach our office on or before 2 pm on 06.10.2025 and will be opened at 3:00 pm on the same day.**

The Manager reserves the right to accept any or reject all the quotations without assigning any reasons.



  
**MANAGER**